

September 9, 2026



Luke Merrill
Mayor
110 First Avenue NW
(763) 444-5512

Construction Includes:

- New Sidewalk
- Curb Replacement
- Street Reclamation & Paving

Construction Schedule:

- *Road Closed to Through Traffic Begins:*
 - September 21, 2026
- *Anticipated Completion:*
November 2026.

Contractor:

North Valley Inc.
20015 Iguana St. NW
Suite #100
Nowthen, MN 55330
Phone: 763-274-2580

Engineer:

Jason W Cook, P.E.
City Engineer
Cell: 763-200-2444
Jason.Cook@bolton-menk.com

Inspector:

Carter Leither
Bolton & Menk, Inc.
Cell: 651-416-6196
Carter.Leither@bolton-menk.com

Project Updates:

Updated construction notices will be sent out as needed.



**BOLTON
& MENK**

Railroad Avenue Improvements Project Construction Notice

Project Summary

The City of Isanti has awarded the 2026 Railroad Avenue Improvements Project to North Valley Inc..

This project includes the construction of a new concrete sidewalk along the east side of Railroad Avenue from Main Street to Palomino Road. The eastern curb line will be reconstructed and shifted in to make room for the new sidewalk. The street surface will be reclaimed and paved.

A sanitary sewer service near the intersection of Palomino Road and Railroad Ave will also be repaired.

A project location map can be found on the back side of this notice.

The following workflow can be anticipated for this project:

- 1) A reclamation machine will grind the existing pavement and blend it with the gravel below.
- 2) The east side curb & gutter will be removed. Curb in a failed condition will be replaced on the west side of the road.
- 3) The storm sewer structures on the east side of the road will be reconstructed, and 2 hydrants will be relocated.
- 4) The concrete curb & gutter and sidewalk will be poured.
- 5) Two layers of bituminous pavement will be placed.
- 6) Topsoil, seed, and mulch will be placed where the existing turf is disturbed.

Project Schedule

Work is anticipated to begin the week of September 21st. Minor work and equipment may begin to show up the week of September 14th. It is anticipated they will complete the work in approximately 7 weeks from when the traffic control goes up.

Please note that construction schedules and operations are controlled by the Contractor and are subject to change based on weather and construction progress.

Traffic Impacts

During construction, the road will be closed to through traffic, and minor delays may occur, but access will be maintained to businesses and residents in the project area.

Please do not park on the street in the project area once the traffic control is in place as your vehicle may be towed to enable the project to be completed.

Thank you for your cooperation during this construction project. If there are any questions or concerns during the project, Jason Cook or Carter Leither will be able to assist you at the phone numbers or emails listed.

Railroad Avenue Improvements Project

City of Isanti

September 2026

