



Mayor Jeff Johnson
City of Isanti
110 1st Avenue NW
(763) 444-5512

2019 Pavement Management Project Construction Notice

Construction Includes:

- Spot Curb Repair
- Spot Sidewalk Repair
- Mill & Overlay
 - 8th Avenue SE
 - Heritage Blvd to School Entrance
- Sealcoat & Fog Seal
 - All City Streets East of TH 65 & South of Heritage Blvd

Construction Schedule:

- *Begin: June 3, 2019.*
- *Mill & Overlay: week of June 10, 2019*
- *Sealcoat: July, 2019.*
- *Final Completion: by September, 2019.*

Contractor:

ASTECH Corp.
PO BOX 1025
St. Cloud, MN 56302
Phone: 302-363-8500

City Engineer:

Bolton & Menk, Inc.
Jason W. Cook, P.E.
Project Manager
Cell: 763-200-2444
Jason.Cook@bolton-menk.com

Project Updates:

The City website will post project updates.



Project Summary

The City of Isanti has awarded the 2019 Pavement Management Project to ASTECH Corporation.

This project includes curb and sidewalk repairs where needed, mill & overlay, sealcoat and fog seal improvements on those City streets east of TH 65 and south of Heritage Boulevard.

Mill & Overlay

8th Avenue SE from Heritage Boulevard to the south school entrance is scheduled for a mill and overlay. You can anticipate the following work flow on this road segment:

- 1) A milling machine will grind the existing pavement down at the lip of curb to allow the new surface to match into the existing curb.
- 2) Once any new concrete curb & gutter has cured, the contractor will sweep the existing road surface, place tack coat, and overlay with a new bituminous surface.

Sealcoat & Fog Seal

All other roadways east of TH 65 and south of Heritage Boulevard are scheduled for a sealcoat with granite chips and a fog seal on top of that. You can anticipate the following work flow on these road segments:

- 1) The contractor will fill the cracks in the pavement and then they will place a tack coat and a large amount of granite chips on the surface.
- 2) They will return to sweep up the loose chips within 3 days of placement, and then a second sweeping will occur within the following week.
- 3) Once all loose chips have been swept up the contractor will place a black fog seal coating over the chips creating a smoother black finish to the roadway that will hold the remaining chips in place.

Project Schedule

The Contractor plans to begin spot removals the week of June 3rd, 2019. The contractor plans to pave the overlay portion of the project on 8th Avenue SE after school is out.

After the 4th of July, the Contractor plans to return to complete the crack fill, sealcoat and fog seal work. This work is anticipated to take 1 week to complete, but will be spread out over the month of July 2019.

Please note that construction schedules and operations are controlled by the Contractor and are subject to change based on weather and construction progress.

Traffic Impacts

During construction the roads will be restricted and minor delays may occur, but access will be maintained to residents.

The Contractor will place no parking signs along the project when work is planned. Please do not park on these streets when posted as your vehicle may be towed to enable the project to be completed.

Thank you for your cooperation during this construction project. If you have any questions or concerns during the project, Jason Cook will be able to assist you at the number listed.